THE MICHIGAN COURTHOUSE

A Planning and Design Guide for Trial Court Facilities

THE MICHIGAN COURTHOUSE

A Planning and Design Guide for Trial Court Facilities

Produced by:

Michigan Court Facilities Standards Project Advisory Committee

In Conjunction with:

State Court Administrative Office
Carter Goble Associates, Inc.
Court Works, Inc.

Produced For:

The Michigan Supreme Court

On the Cover:
The 52nd District Court - 4th Division, Troy, MI and the 42nd District Court - 1st Divisic
Photos Courtesy of Thomas Strat & Associates

TABLE OF CONTENTS

The Michigan Courthouse

INTRODUCTION

STUDY PURPOSE

I.1 **Michigan Court Facilities Standards Project Advisory Committee Membership** I-1

I.2 **Consultants to the Project** I-1

I.3 **Study Purpose** I-1

I.4 **Study Scope** I-2

I.5 **Court Organization** I-3
- **I.5.1** **Michigan Supreme Court** I-3
- **I.5.2** **Michigan Court of Appeals** I-4
- **I.5.3** **Circuit Court** I-4
- **I.5.4** **Michigan Court of Claims** I-5
- **I.5.5** **Probate Court** I-5
- **I.5.6** **District Court** I-5
- **I.5.7** **Municipal Court** I-6

SECTION 1

THE PLANNING PROCESS

1.1 **FACILITY PLANNING AND DESIGN PROCESS** 1-1
- **1.1.1** **Getting Organized** 1-3
- **1.1.2** **Who Should Participate** 1-3
  - *1.1.2.1 Project Manager* 1-4
  - *1.1.2.2 Functions of the Committee* 1-4
  - *1.1.2.3 Selecting Consultants and Creating the Project Team* 1-4
- **1.1.3** **Preparing the Request for Proposal and Selecting an Architect** 1-5

1.2 **Needs Assessment** 1-7
- **1.2.1** **Forecasting and Determining Needs** 1-7
- **1.2.2** **Methodology** 1-8
- **1.2.3** **Master Planning and Determination of Alternative Solutions** 1-9
  - *1.2.3.1 Assessment of Short and Long Term Needs* 1-10
  - *1.2.3.2 Evaluation of Existing Space* 1-10
  - *1.2.3.3 Alternatives to Address Space Needs* 1-11
  - *1.2.3.4 Development of the Implementation Plan* 1-11

1.3 **The Program Statement** 1-12
- **1.3.1** **Step 1 – Operational Framework** 1-13
- **1.3.2** **Step 2 – Spatial Framework** 1-14
- **1.3.3** **Step 3 – Financial Framework** 1-19

1.4 **The Design Steps** 1-25
- **1.4.1** **Step 1 – Schematic Design** 1-25
- **1.4.2** **Step 2 - Design Development** 1-26

1.4.3 Step 3 – Construction Documents 1-28
1.4.3.1 Conduct Detailed Reviews of the Construction Documents 1-29
1.4.3.2 Final Cost Estimate 1-29
1.4.3.3 Coordination of the Construction Bidding Process 1-29
1.4.3.4 Conduct Pre-Construction Conference 1-29
1.4.4 Step 4 – Construction Administration 1-29

1.5 Construction Methods 1-30
1.5.1 Building Approaches 1-30
1.5.2 Building Techniques 1-31
1.5.3 Life Cycle Considerations 1-32
1.5.4 Project Organization 1-32
1.5.4.1 Description of Construction Phase Services 1-33
1.5.4.2 Construction Communication Procedures 1-34
1.5.4.3 Conduct Final Inspection 1-35
1.5.4.4 Identify and Coordinate All Construction Warranty Provisions . 1-35

1.6 The Project Management Cycle 1-35
1.6.1 Construction Manager (CM) 1-37
1.6.2 Program Manager (PM) 1-38
1.6.3 Construction Manager/General Contractor (CM/GC) 1-38

1.7 Financing Options 1-39
1.7.1 Public Financing 1-39
1.7.1.1 Bonds (pay-as-you-use) 1-39
1.7.1.2 General Obligation Bonds 1-40
1.7.1.3 Non-guaranteed Bonds (Revenue Bonds) 1-40
1.7.2 Taxes 1-40
1.7.2.1 Property Tax 1-41
1.7.3 Private Financing 1-42
1.7.3.1 Lease-Purchase 1-42
1.7.3.2 Certificates of Participation (COPS) 1-42

1.8 Conclusion 1-43

SECTION 2
GENERAL COURT DESIGN ISSUES

2.1 Issues of Court Organization and Administration 2-1
2.1.1 Function vs. Jurisdiction 2-1
2.1.2 Judicial Assignments and Calendaring Systems 2-2
2.1.3 Court Divisions and Jurisdiction Specialization 2-2
2.1.4 Ratio of Courtrooms to Judges 2-3
2.1.5 Specialized Courtrooms 2-3

2.2 Renovation or New Courthouse 2-4
2.2.1 When to Renovate and When to Build New 2-4
2.2.2 Problems Usually Encountered 2-5
2.2.3 Types of Facilities 2-6
2.2.4 Phasing of the Project 2-6

2.3 Site Location 2-7
2.3.1 Site Size 2-7

2.4 Image of the Court 2-8
2.4.1 Accessibility 2-10
2.4.2 Parking 2-10
2.4.3 Vehicular Traffic 2-11
2.4.4 Exterior Lighting 2-11
2.4.5 Building Circulation and Zoning 2-11
2.4.6 Public Zone 2-12
2.4.7 Private Zone 2-13
2.4.8 Secure Zone 2-13
2.4.9 Interface Zone 2-14
2.4.10 Service Zone 2-14

2.5 User Requirements 2-14
2.5.1 Public Accessibility 2-14
2.5.2 Support Services 2-15

2.6 Security 2-15
2.6.1 Entrance Screening 2-16
2.6.2 Alarm Systems 2-16
2.6.3 Intrusion Sensors 2-17
2.6.4 Fire Detection 2-17
2.6.5 Access Control 2-17
2.6.6 Video Surveillance 2-18
2.6.7 Secure Circulation 2-18
2.6.8 Public Address 2-18
2.6.9 General Security Measures 2-18

2.7 Growth Management - Planning for Flexibility and Growth 2-18

2.8 Court Technology and Implications for Courtroom Design 2-22
2.8.1 Building Infrastructure 2-22
2.8.1.1 Computer Systems 2-22
2.8.1.2 Telephone/Data 2-22

2.9 Common Areas 2-23
2.9.1 Lobby 2-23
2.9.2 Court Support Areas 2-23
2.9.3 Workspaces 2-23
2.9.4 Conference/Meeting Rooms 2-24
2.9.5 Courtroom 2-24

2.10 Overall Design Considerations 2-26
2.10.1 Video Evidence 2-26
2.10.2 Video Appearance 2-26
2.10.3 Sound Amplification 2-27
2.10.4 Audio Evidence 2-27
2.10.5 Lighting 2-27

2.10.6 Temperature Controls 2-27
2.10.7 Bench 2-28
2.10.8 Litigant / Counsel Tables 2-28
2.10.9 Jury Box 2-28
2.10.10 Witness Stand 2-28
2.10.11 Clerk/Reporter Station 2-28
2.10.12 Bailiff Station 2-29

2.11 Conclusion 2-29

SECTION 3

COURTHOUSE DESIGN CRITERIA

3.1 The Judicial Set 3-1
3.1.1 Jury Trial Courtrooms 3-2
3.1.1.1 Imagery and Function 3-2
3.1.1.2 Shape 3-2
3.1.1.3 Size 3-3
3.1.1.4 Environment 3-5
3.1.1.5 Adjacencies and Circulation 3-6
3.1.1.6 Accessibility 3-6
3.1.1.7 Security 3-7
3.1.1.8 Furnishings and Finishes 3-7
3.1.2 Courtroom Technology 3-7
3.1.2.1 Court Reporting - Audio and Video Equipment 3-8
3.1.2.2 Video and Tele-communications 3-8
3.1.2.3 Office Automation and Case Management Systems 3-8
3.1.2.4 Legal Research 3-9
3.1.2.5 Presentation Systems 3-9
3.1.2.6 Accessibility Systems 3-9
3.1.2.7 Lighting Controls 3-10
3.1.2.8 Security 3-10
3.1.2.9 Other Equipment 3-10
3.1.3 The Judge's Bench 3-10
3.1.4 Clerk's Station 3-12
3.1.5 Witness Stand 3-13
3.1.6 Jury Box 3-14
3.1.7 Litigant / Counsel Tables 3-16
3.1.8 Lectern 3-17
3.1.9 The Bailiff's Station 3-18
3.1.10 Spectator Seating 3-18
3.1.11 Witness Waiting Rooms 3-20
3.1.12 Attorney/Client Conference Rooms 3-20
3.1.13 Entry Vestibule 3-21
3.1.14 Jury Deliberation Rooms 3-21
3.1.15 Judges' Chambers 3-23
3.1.15.1 Security 3-23
3.1.15.2 Environment 3-24
3.1.15.3 Furnishings and Finishes 3-25
3.1.15.4 Circulation and Adjacency 3-25

3.1.15.5 Technological Applications 3-25
3.1.15.6 Support Spaces 3-25

3.2 Court Administration 3-26

3.3 Clerk of Court 3-27
3.3.1 Circulation and Adjacency 3-27
3.3.2 Handicapped Access 3-27
3.3.3 Administrative Offices 3-28
3.3.4 Organization and Layout 3-28
3.3.5 Security 3-33
3.3.6 Information Desk 3-33
3.3.7 Public Counter 3-33
3.3.8 Case Processing 3-35
3.3.9 Data Processing 3-35
3.3.10 Records Management 3-36
3.3.11 Records Storage 3-37
3.3.12 Vaults 3-39
3.3.13 Staff Lounge 3-39
3.3.14 General Guidelines for Clerk's Office 3-39

3.4 Family Division (including friend of the court) 3-40

3.5 The Prosecuting Attorney (optional) 3-42

3.6 Magistrates and Referee Hearing Rooms 3-45
3.6.1 Regional Diagnostic Hearing Room 3-45

3.7 Probation Offices 3-45

3.8 Judicial Support Functions 3-46
3.8.1 Jury Assembly 3-46
3.8.2 Grand Jury 3-47
3.8.3 Law Library 3-47
3.8.4 Attorney Lounge (optional area) 3-49
3.8.5 Law Enforcement Waiting (optional area) 3-50
3.8.6 Press and Media Support Facilities (optional area) 3-50

3.9 Building Support Functions 3-51
3.9.1 Loading Dock 3-51
3.9.2 Custodial and Maintenance Services 3-52
3.9.3 Service Elevator 3-52
3.9.4 Trash and Recycle Removal 3-53
3.9.5 Building Communication Backbone 3-53
3.9.6 Telecommunications and Data Entry Rooms 3-53
3.9.7 Telecommunications Systems and Information Technology Room 3-54
3.9.8 Telecommunications Closets 3-54
3.9.9 Electrical Power and Electrical Closets 3-55
3.9.10 Vending and Food Service 3-55
3.9.11 Shared Conference Facilities 3-55
3.9.12 Building Management and Storage 3-55

3.9.13 **Lobby** 3-56
3.9.14 **Public Circulation, Elevators, and Escalators** 3-56
3.9.15 **Public Restrooms** 3-57
3.9.16 **Day and Child Care** 3-57
3.9.17 **Mail Room** 3-58
3.9.18 **Security Office and Fire Control Center** 3-58
3.9.19 **Central Security Control and Security Stations** 3-58
3.9.20 **Central Prisoner Holding and Transport** 3-59
3.9.21 **Court Floor Holding Areas** 3-60

3.10 **Conclusion** 3-61

3.11 **Summary of Minimum Space Requirements** 3-62

APPENDIX

SECTIONS A1 - A10

Sec. A1 **Glossary of Terms** A1-1

Sec. A2 **Selected Michigan Statutes, Court Rules, and Supreme Court Administrative Orders Concerning Court Facilities** A2-1

Sec. A3 **Attorney General Opinion #5980** A3-1

Sec. A4 **Courthouse Facility Checklist** A4-1

Sec. A5 **ADA Title II Self Evaluation** A5-1

Sec. A6 **Request for Qualifications (RFQ's) and Request for Proposals (RFP's) Process and Examples** A6-1

Sec. A7 **Sample Standard Forms 254 and 255** A7-1

Sec. A8 **American Institute of Architects Contract Information** A8-1

Sec. A9 **Resource List** A9-1

Sec. A10 **Bibliography** A10-1